

**BUSINESS CASE SUMMARY** 

Page: 3 of 19 Filed 2013-09-2

EB-2013-0321

Ex. F2-3-3 Attachment 1 Tab 6

#### EQ Discovery Work & Scope Reduction Project 16 - 38458 Partial Release Business Case Summary D - BCS - 03651-10006 - R000

#### **RECOMMENDATION:**

42.3

Approval is requested for a Partial Release of 45.0 M\$ OM&A (including contingency) to allow the Environmental Qualification (EQ) Discovery Work and Scope Reduction Project to continue the work required for Darlington to comply with the EQ requirements in its Power Reactor Operating Licence (PROL) and Design Basis. (This amount includes 9.8 M\$ released previously under a Developmental Release). Total project cost estimate is 75.7 M\$.

The business objective of this project is to align Darlington with the EQ requirements of its design basis and PROL. This project is a follow-up to Project 16-38457 and will execute EQ scope reduction initiatives. The deliverables for this partial release are outlined in section 4 of this Business Case Summary. This project is required for Darlington to be in compliance with the EQ conditions of its PROL by December 31, 2010.

The previous release was used to:

- Initiate / Complete conceptual and preliminary engineering activities for the required modifications.
- Initiate the required revisions to the EQ design basis document set.

The funding under this release will be used to:

- Complete the detailed engineering activities for the required modifications.
- Complete the required revisions to the EQ design basis document set.
- Complete the analysis required to determine if the project's scope can be reduced in order to reduce the cost of the project and the size of Darlington's sustaining EQ program.
- Initiate the installation activities for selected modifications.
- Execute completion assurance activities for selected equipment.

\$000's (incl contingency)	Type	LTD 2008	2009	2010	2011	2012	2013	Later	Total
Currently Released	Developmental	***************************************	9,779	17 299	229				9.779
Requested Now	Partial		15,122	20,121				2 3 4	35,243
Future Funding Req'd	Full			843 20,121	10,525			3,4,3	
Total Project Costs		-	24,901	40,242	10,525			351	75,668
Non Project Costs					10,020			-	75,000
Grand Total		•	24,901	40.242	10.525			_	75,668
Investment 1 Regulator	■ *** * * * * * * * * * * * * * * * * *	Clas OM8	is i	Ni		1774	RR /A	Discounte N	d Payback

Non Project Costs							
Grand Total		-	24,901	40.242	10,525		
Investment Regulato	- F(F) 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	Clas OM8		NP -36.0	V		IRR N/A
Submitted By:				tation and the section of the sectio	and the second s	handle to the second second second	destruited in the state of the
Spinet	Pobles	2009-	0575				

W. Robbins Senior Site Vice-President Darlington

Date:

Finance Approval:

Line Approval (Per OAR Element 1.1 Project in Budget):

D. Hanbidge

J. Hankinson

Date:

VP, Corporate Finance

President & CEO



Page:

File 0.5 1 3-09-27

EB-2013-032

**BUSINESS CASE SUMMARY** 

Ex. F2-3-3 Attachment 1 Tab 6

#### 2/ BACKGROUND & ISSUES

The Ontario Power Generation Nuclear (OPGN) Environmental Qualification (EQ) program establishes an integrated and comprehensive set of requirements that provide assurance that essential equipment can perform as required if exposed to harsh design basis accident conditions and that this capability is preserved over the life of the plants. Under Condition 7.1 of its Power Reactor Operating License (PROL), Darlington must implement a program that is traceable, auditable and meets the OPGN requirements for EQ.

Requirements for EQ at the Darlington Nuclear Generation Station (DNGS) were first spelled out in the Construction License and formalized in 1978 with the first issue of the Design Guide. EQ was in its infancy and formal EQ requirements did not apply to other CANDU stations. In the absence of Corporate, or National standards for EQ, a Darlington specific program manual was developed to provide governance for implementation of EQ. The list of equipment required to be qualified, the EQ Safety Related Component List (EQSRCL), was developed in a non-procedural, non-auditable manner and EQ was implemented at DNGS over the period of 1986 to 1992.

The EQ program was handed over from Design & Construction to Operations in 1992. Lack of focus on the EQ sustaining program and the resultant degradation in component condition prompted the IIP EQ Restoration Program (Project EN009) in 1997. In November 1999, the CNSC proposed an amendment that became a part of the Darlington's PROL requiring that the station provide evidence that required systems, components, protective barriers and structures in the facility are environmentally qualified by June 30, 2004.

The IIP Project was closed in 2001, with some scope necessary to comply with the PROL Condition outstanding. The transition plan identified the work to be completed, with an expectation that the majority of the issues would be completed by the end of 2003.

In May 2003, the CNSC provided acceptance criteria to clarify what was required to satisfy the PROL condition. At the direction of the Chief Nuclear Engineer the remaining EQ work was divided into two projects: one to complete activities necessary to satisfy the PROL condition due June 30, 2004, and a second to complete CNSC EQ commitments due after June 30, 2004 and establish a sustaining EQ Program.

The EQ Recovery Project (16-38411), which was completed June 30, 2004, involved completing the outstanding EQ assessments, completing gap analysis for components with a limited life and scheduling the resolution of issues remaining after June 30, 2004. Upon completion of project 16-38411, another project, 16-38457 EQ Closure and Component Replacement was initiated to resolve the outstanding issues by December 31, 2010.

The EQ Closure and Component Replacement Project (16-38457) was initiated in 2004. Under this project Darlington has followed the OPGN EQ list development process to update its EQSRCL; this process provides full traceability and compliance with the EQ design basis. As a result of an unexpected large number of deficiencies being identified a scope optimization study was conducted on Darlington's EQ program which made several recommendations on how Darlington could reduce the size of its EQ program.

This project is a follow up to Project 16-38457 established to execute EQ scope reduction initiatives. Under the developmental release conceptual / preliminary engineering activities have been initiated and revisions to the EQ design basis document set have been initiated. Analysis has been completed to verify the validity of the Critical Breaks Approach to EQ which was established through NSS analysis under Project 16-38457. While this approach does represent a significant reduction in scope it also identified further opportunities for scope reduction.

As outlined in section 4 this partial release will:

- 1. Continue with the necessary engineering work to implement the critical breaks approach.
- 2. Initiate the installation of the modifications required to implement the critical breaks approach.
- 3. Complete the necessary analysis to determine if the scope of the project can be further reduced.
- 4. Complete the required revisions to affected documents.
- Execute completion assurance activities.



Page:

Filed: 2013-09-27 EB-2013-0321 5 of 19-20

**BUSINESS CASE SUMMARY** 

Attachment 1 Tal

#### 3/ ALTERNATIVES AND ECONOMIC ANALYSIS

		Alt 1 (Reco	ommended)	Alt 2	Alt 3	Alt 4	Alt 5
\$ 000's	Base Case	Full Cost	Incremental Cost				
Revenue							
OM&A		(75,668)		(71,581)	(68,981)		
Capital				(11,001)	(00,501)		
Present Value (PV)		(39,887)	(35,993)	(37,762)	(36,411)		
Net Present Value (NPV)	N/A	(39,887)	(35,993)	(37,762)	(36,411)		
Internal Rate of Return (IRR) %	N/A		(00,000)	(01,102)	(00,411)		
Discounted Payback (Yrs)	N/A		****				

# Base Case: Not Recommended - Fully Implement EQ to Group 1 & Group 2 Equipment

The base case is to complete the necessary modifications in order to fully EQ all Group 1 support components as per the existing design basis. This is not recommended since it would significantly increase the cost of the project and would result in a sustaining program that the station would not be able to maintain with their current resource levels.

#### Alt. 1: Recommended - Implement Critical Breaks Approach

The Critical Breaks Approach was developed by NSS and involves implementation of a reduced set of modifications which will ensure that any remaining EQ inadequacies will have a negligible safety impact. The modifications include work on critical breakers and HVAC control circuits in order to support both divisions of Class III power.

This is the recommended approach since it involves implementation of a reduced set of modifications with minimal impact on the current design / licensing basis. In addition to the necessary modification work analysis will be completed to determine if the scope of the project can be reduced further.

# Alt. 2: Not Recommended - Implement EQ to Group 2 Equipment Assisted by Standby Generators

This approach assumes that Group 2 heat sinks are qualified for secondary-side line breaks and portions of Class III power are also credited to support Group 2 heat sinks. This would involve a limited set of modifications to the Class III system to allow the Standby Generators to support Group 2. This approach is not recommended at this time because it is based on preliminary analysis and further work is required to verify the assumptions made.

## Alt. 3: Not Recommended - EQ only Group 2 Equipment

This approach assumes that only Group 2 heat sinks will be qualified for secondary-side line breaks. All EQ scope related to Group 1 heat sinks would no longer be required. While this approach significantly reduces the project scope it is not recommended since it would also significantly reduce the stations operating margin.

Alt 4: Not Recommended -

Alt. 5: Not Recommended -



Page:

Filed: 2013-09-27

**BUSINESS CASE SUMMARY** 

Ex. F2-3-3 Attachment 1 Tab 6

#### 4/ THE PROPOSAL

32.5 ADP

The proposal is for the partial release of \$35.2 M to allow the EQ Discovery work and Scope Reduction Project to:

- 1. Complete detailed design activities and initiate installation activities to environmentally qualify the following:
  - Deaerator Storage Tank Level Transmitters
  - Solenoid Valves for Low Pressure Service Water Temperature Control Valves
  - Class III Power
  - Class IV Power
  - Heating, Ventilation and Air Conditioning equipment associated with Steam Protected Rooms
  - Power Supply (Motor Control Center 363) for Fan 29
  - Service Water Pneumatic Valve 501
  - Fuelling Machine D<sub>2</sub>0 Injection Valves
  - Auxiliary Boiler Feed Pumps
  - Shutdown Cooling Temperature Control Valves
  - Primary Heat Transport pressurizer heaters
  - Control Power (Motor Control Center 259/260) for Fan 1/Fan 2/Fan 3/Air Conditioning Unit 1
  - D<sub>2</sub>0 Recovery Isolation Valve
  - Wet Room Transmitters

In addition, analysis and modification work will be completed as required to credit the Column Line 11 wall as a steam barrier.

Essential project scope comprises equipment and systems which must be qualified to satisfy the license condition. This essential scope will be given priority to ensure that all field modifications on these systems are completed by December 31, 2010 in order to meet the license condition. The balance of scope related to equipment and systems which must be qualified in order to ensure the station has sufficient operating margin.

- 2. Complete analysis required to pursue scope reductions associated with reactor heat sink qualification methodology (from the "Critical Breaks Approach including Group 1 Heat Sinks" to "Group 2 Heat Sinks assisted by Standby Generators").
- 3. Complete the necessary updates to:
  - Technical Basis Documents
  - EQ List Development Packages
  - EQ Assessment Part 1's (evaluation of equipment EQ requirements, including configuration, maintenance, and replacement requirements)
  - EQ Assessment Part 2's (establishes basis for EQ of a manufacturer's component by evaluation of test and analysis documentation)
  - Room Conditions Manual
  - Safety Report
  - Operation / Maintenance document set
- 4. Perform the required completion assurance activities. This will include field verification walk-downs and documentation and PassPort reviews.

All scope additions and changes are reviewed by a Darlington EQ Steering Committee for approval, in addition to normal Project Approval Committee and Site Management Board meetings. In addition, field walk downs are being conducted to resolve outstanding configuration management issues.



Page:

7 **5ifet(9**2013-09-27 EB-2013-0321

**BUSINESS CASE SUMMARY** 

Ex. F2-3-3 Attachment 1 Tab 6

#### 5/ QUALITATIVE FACTORS

Environmental Qualification compliance and sustainability are license requirements. Qualitative benefits of the project are:

- 1. An improved ability to contain and minimize damage or loss of the asset due to a harsh design basis accident.
- 2. An increase in public and employee safety.
- 3. A manageable EQ program which Darlington will be able to sustain.

# ONTARIO GENERATION

OPG Confidential Page:
BUSINESS CASE SUMMARY

8 of 19

6/ RISKS (see Attachment D for details)

			S2)	of t	6u	ItsA	Risk					7									_	<b>∞</b>					File	ed:	201 013-0	3-09-	-27 <b>9</b>
				, (ety	Sal	lear	onN				•	4									***************************************	∞					Ex	. F	013-0 2-3-3 hmer	_	Tallo (
				Ju	әш	iron	νu∃					<b></b>								***************************************		2								+	~
noact			/	iteti	2S 8	3 411	Hea	5	5			<b>.</b>									~~~~	7					resident de la companya de la compa			_	0
itv x lr				9	(Jo	islu	Бәу	(iting	n inga							***********					***************************************	9						~		+	Ω
Probability x Impact		noii	etu	dəy	əte	pors	Cor	After Mitigation				<del></del>					-	***************************************				4				~	***************************************		·····		0
4						lity	gns	1				t	·			***************************************					***********	~					***************************************	····		<b>,</b>	~
					əļi	npə	yos.				5	<u>,</u>							***	***************************************		∞								+	ဖ
					6	out	Fini				α	>									***************************************	~			Marie in manuscript and					+,	~
		(	52	ot t)	Gui	BA )	IsiA				2	3										<del>ن</del>								<b>†</b> ;	<u></u>
			ý	fety	s2 1	ieal:	υN			***************************************	4	r										5			<del>*************************************</del>				***************************************	0	က
*				ļu	อเมเ	ioni	/u3				4	+	***************************************					······································		•••		က	· · · · · · · · · · · · · · · · · · ·							1	
Impac			Á	afet	S 8	чн	SəH	gatio	2		4	•					•••••					က		<del></del>							
Probability x Impact				,	not	alula	Rei	Before Mitigation			œ	)									į	3	***************************************							-	
Probat		uo	itati	şebr	H etr	por	100	Sefore			4	-									(	ထ			***************************************					,	CO
	L					ytile	ηŊ	"			4										c	.ro					***************************************	********		,	n
					əļr	pəu	PS		-		20	i								~~~	·	22								L	ဂ
	L				ə	suc	ni7				4										•	n								۰	ກ
High = 10 to 26		w	2	90	16	9	22	Activities		riovided design contracts can be released in a manner that would necessitate additional funding the project will submit a	from the 2010	on project	ance design	being used to	4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	Weekly meetings are being held with all Design Agencies to monitoring the	anvissies	and increase	A dedicated EQ Design Section within		r meetings with		gare being	advanced.	being .	if completing	Group 2	It. Allowing the	modifications to Group 1 systems to	e being	rly in the
Hgh.		4	8	10	12	8	4	Mitigating Act	oto coto	riovided design contracts can be rele in a manner that would necessitate additional fundion the project will subs	PCRAF to transfer funding from the 2010	budget and/or draw down on project	contingency in order to advance design work.	Design Agencies are being used	expedite all designs. Mookly mootings pro	weekiy ineetings are being heid all Design Agencies to monitoring	schedule and resolve any issues	arise.	sated EQ Desig	the Design Agencies.	The project has regular meetings	all stakeholders.	Workplans / assessing are being	design so work can be advanced.	The PROL condition is being	reviewed to determine if completing	the modifications on all Group 2	s would satisfy	modifications to Group 1 systems	Long lead materials are being	dentified and order early in the
4 to 9	Impact	8	15	12	6	9	3	M	Drough of	in a mannel	PCRAF to t	budget and	contingency work.	1. Design	nadya c		sched	which arise.	3. A dedic	the De	4. The pro		5. Workpl	design	6. The PF	review	the mo	system	modific	1. Long le	identifie
Medium = 4 to 9		2	10	80	9	4	2	ion	avior la mo	ow all design sar end which bility to	/ December			oleted prior to	Pilarice Willi															ue to	ation
Low = 1 to 3			2	4	3	2		Risk Description	2009 cash-flow may not allow all design	work to be completed by year end which could impact the projects ability to	complete all installations by December			Modifications are not completed prior to December 31, 2010 in compliance with	000															Unavailability of materials due to	compressed design / installation
LOW			20	4	8	2	-	4	19 Cach	k to be	nplete a	oʻ		dification ember	the PROI	i 2														vailabili	pressec
				ility	psp	Prol			S	§ № 8	00	2010.		N S S S S	4	5														Una	8 E



of 19

တ

Page:

BUSINESS CASE SUMMARY

Risk Rating (1 to 25)

Filed: 2013-09-27 EB-2013-0321 Ex. F2-3-3 Nuclear Safety S a ന S Attachment Teato 6 Environment N N ന S N က Probability x Impact After Mitigation Health & Safety  $\alpha$ N က N  $\alpha$ က Regulatory 2 N က N N m Corporate Reputation N S က N C) က Quality Q C) က N 4 က Schedule ∞ 4 ဖ 4 Θ ന Finance N က က S က Risk Rating (1 to 25) 2 2 S O G O **Nuclear Safety** က က ന ന 4 က Environment က က က ന N က Probability x Impact **Before Mitigation** Health & Safety က က က က N က Regulatory က က က က N က Corporate Reputation ന က ന က N ဖ Quality ന က က ω ന Schedule 57 თ တ 5 S O Finance က က က ဖ N က Supply Chain has appointed a SPOC Where possible Design Agencies are walkdowns showed that no significant additional vendors with EQ expertise. Issues with obtaining support from internal Contingency has been included to account will be specified if deemed necessary. Additional testing / receipt inspection developed for expected deficiencies resources are communicated upward so station management can set appropriate Standard repairs details have been Use of qualified suppliers / 3rd party The project is utilizing all of OPGs to assist in material procurement. Use of OPG Source Surveillance 2 account when selecting material. completed by internal resources. S inspection campaigns at PNGS OPEX from D811 / 2008 online taking material lead times into Mitigating Activities preferred vendors as well as Use of OPEX from previous Selected designs are being for potential cost increases. œ 4 design phase. dedicators. work priorities. DNGS. Impact က 6 9 Medium = 4 to 9 αi က် αi αi αi က Cost estimates for several designs were Material quality issues with components based on preliminary information since Discovery of significant issues during being replaced causing delays to the Unavailability of OPG support group 2 œ 9 4 Unavailability of Design resources. field verification walkdowns during Significant discoveries during the conceptual design has not been Risk Description nspection of column line 11. schedule / cost increases. S 4 3 2 Low = 1 to 3 schedules completed. esonices 3 N Probability

 $\infty$ 

4

ဖ

4



BUSINESS CASE SUMMARY

10 of 19

Page:

Risk Rating (1 to 25) 4 σ **Nuclear Safety** N N Environment <∪ N Probability x Impact After Mitigation Health & Safety N N Regulatory S N Corporate Reputation  $\sim$ Q Quality N N Schedule 4 ω Finance N N Risk Rating (1 to 25) 9 ω **Nuclear Safety** S 4 Environment  $\alpha$ 4 Probability x Impact Before Mitigation Health & Safety Q 4 Regulatory N 4 Corporate Reputation N 4 Quality  $\alpha$ 4 Schedule 9  $\infty$ Finance N  $\infty$ are scheduled to be completed by the Contingency plans will be developed completed to identify if there are any revised on an accelerated schedule. prior to the 2010 outages based on Remaining EQLDP / TBD revisions All high risk EQLDP revisions have completed to identify any potential EQA Part 2s are being prepared / OPEX from previous walkdowns. 2 preparation / revision. (TCD: Q2-5 A review of the TBDs has been Mitigating Activities A feasibility analysis is being risks associated with EQA findings are expected. areas of concern. been completed. œ end of 2009. Impact 3 6 9 3 Medium = 4 to 9 •  $\alpha$ i  $\alpha$ i က Identification of new modification scope qualifiable through an EQA is found not to be. N 8 9 4 Equipment which is believed to be Risk Description during EQLDP / TBD revisions. 2 4 3 2 Low = 1 to 3 D1041 / D1021 3 5 4 N Probability

Filed: 2013-09-27 EB-2013-0321 Ex. F2-3-3 Attachment 1 Tab 6



4\_\_\_\_

Page:

11 of 19

**BUSINESS CASE SUMMARY** 

Filed: 2013-09-27 EB-2013-0321 Ex. F2-3-3

Attachment 1 Tab 6

### 7/ POST IMPLEMENTATION REVIEW PLAN

Type of PIR:	Targeted Final AFS	Targeted PIR Approval	PIR Responsibility
	Date:	Date:	(Sponsor Title)
Simplified	TBD in Next Release	TBD in Next Release	Director of Engineering

	Measurable Parameter	Current Baseline	Targeted Result	How will it be measured?	Who will measure it? (person / group)
1.					
2.					
3.					
4.					
5.					



Page:

12 of 19

**BUSINESS CASE SUMMARY** 

Filed: 2013-09-27 EB-2013-0321 Ex. F2-3-3

Attachment 1 Tab 6

#### Appendix "A"

#### Glossary (acronyms, codes, technical terms)

AFS: Available for Service BCS: Business Case Summary

CNSC: Canadian Nuclear Safety Commission DNGS: Darlington Nuclear Generating Station

EQ: Environmental Qualification

EQA: Environmental Qualification Assessment

EQLDP: Environmental Qualification List Development Package
EQSRCL: Environmental Qualification Safety Related Components List

FM: Fueling Machine

HVAC: Heating, Ventilation and Air Conditioning

IEV: Impact on Economic Value
IRR: Internal Rate of Return
IPP: Integrated Improvement Plan
LPSW: Low Pressure Service Water

LT: Level Transmitter

LTD: Life to Date

MCC: Motor Control Center N/A: Not Applicable NPV: Net Present Value

NSS: Nuclear Safety Solutions Inc.
OAR: Organizational Authority Register

OM&A: Operating, Maintenance, and Administration

OPEX: Operating Experience
OPG: Ontario Power Generation

OPGN: Ontario Power Generation Nuclear

PCRAF: Project Change Request Authorization Form

PEP: Project Execution Plan
PHT: Primary Heat Transport
PIR: Post Implementation Review

PNGS: Pickering Nuclear Generating Station
PROL: Power Reactor Operating License

PV: Pneumatic Valve
SG: Standby Generator
SPOC: Single Point of Contact
T&M: Time and Material

TBD: Technical Basis Document



BUSINESS CASE SUMMARY

Page: 13 of 19

Filed: 2013-09-27 EB-2013-0321

Ex. F2-3-3 Attachment 1 Tab 6

# Appendix "B"

### **Project Funding History**

\$ 000's		All	Existing a								
Release Type	Month	Year	2009	2010	2011	2012	2013	2014	2015	Later	Total
Developmental		and the second second	9,779	17399	A 40						9,779
Partial			24,901	20,121	7					42300	45,022
											0
											0
						TO THE PERSON NAMED IN COLUMN TO THE					0
											0
		A CONTRACTOR OF THE CONTRACTOR									0
											0
		1		1		4			Aciana		
LTD Spent	Mar	2009									0



Page: 14 of 19 Filed: 2013-09-27

888555

EB-2013-0321 Ex. F2-3-3

**BUSINESS CASE SUMMARY** 

Ex. F2-3-3 Attachment 1 Tab 6

#### Appendix "C"

#### **Financial Model – Assumptions**

#### **Financial Assumptions:**

Discount Rate	7%	Cost Escalation (yr)	None	SR & D Opportunity	No
Progress Payments	No	Foreign Currency	No	Retainer Fee	No
Income Tax Rate	Non Generation	PST	N/A	Interest Rate (Capital)	OMA N/A
Depreciation Rate (Capital)	N/A	Leasing	No	Indexed Priced Contract	No

Comments:

#### **Project Cost Estimate:**

Design Complete	Up to - 40%	Quality of Estimate	Budget + 30% to - 15%	3rd Party Estimate	No
Reviewed by Sponsor	No	OPEX used	Yes	Lessons Learned	Yes
Similar Projects	Yes	Budgetary Quote(s)	No	First Unit Actual Used	No
Cost Sharing	No	Contracts in place	Some in place	Competitive Bid	No
Fixed Price Contract	No	Fee for Service	No	Firm Vendor Proposal	No

Comments:

#### **Rationale for Cost Classification:**

#### **Generation Plan Assumptions:**

Station	Unit	E(	)L	MW	Capacity		Planned	Outages	for Project	Work (eg	P1071)	
Diakorina A	1	N/A	T				T	i i	1		T	<u> </u>
Pickering A	4	N/A										
	5	N/A										
Diekering D	6	N/A										
Pickering B	7	N/A				***************************************						
	8	N/A										
	1	Jun	2018									
Darlington	2	Sep	2016	935	0.00/				<b>†</b>			
Darmiyton	3	Mar	2020	335	88%							
	4	Dec	2021									

#### Comments:



BUSINESS CASE SUMMARY

Page: 15 of 19 Filed: 2013-09-27

EB-2013-0321 Ex. F2-3-3

Appendix "C"

## <u>Financial Model – Assumptions</u> <u>Impact on Operations</u>

\$000's	Present	2009	2010	2011	2012	2013	2014	2015	Later	Tota
Rate KWH										
Probability										0.0%
Consequence										0
Risk										0
Other										0
Base Case	0	0	0	0	0	0	0	0	0	0
Probability										0.0%
Consequence				L				7		0
Risk										0
Other										0
Recommendation	0	0	0	0	0	0	0	0	0	0

#### **Comments:**

\$000's	Present	2009	2010	2011	2012	2013	2014	2015	Later	Total
Base OM&A	0.000									0
Outage OM&A										0
Project OM&A										0
Base Case	0	0	0	0	0	0	0	0	0	0
Base OM&A										0
Outage OM&A										0
Project OM&A		24,901	40,242	10,525						75,66
Recommendation	0	24,901	40,242	10,525	0	0	0	0	0	75,668
Net Impact		24,901	40,242	10,525	0	0	0	0	0	75,668

#### **Comments**:

Cash flows and committed milestones assume that this BCS receives OAR approval by 15Jun2009.

Page: File of 2613909-27

**BUSINESS CASE SUMMARY** 

EB-2013-0321 Ex. F2-3-3

Attachment 1 Tab 6

# EQ Discovery Work & Scope Reduction Project 16 - 38458 Partial Release Business Case Summary D - BCS - 03651 - 10006 - R000

### **Attachment "A"**

#### **Project Cost Summary**

				91000.00						
	\$000's OM&A	LTD 2008	This BCS 2009	This BCS 2010	Future 2010	Future 2011	2012	2013	Later	Total
	Project Mgmnt & Support		2,412	1,993	1,993	3,450				9,847
	Engineering	***************************************	13,914	3,716	3,716	2,575	DOVELO-PARTICIONAL PROPERTY PROCESSOR STORAGE	A STATE OF THE PARTY OF THE PAR		23,921
	Procurement	N/VIII/A/A/A-A-A-A-A-A-A-A-A-A-A-A-A-A-A-A-	564	1,244	1,244	***************************************		***************************************		3,052
	Construction		1,011	6,919	6,919		THE PROPERTY OF THE PROPERTY O	***************************************		14,848
Sc	Other		500	1,500	1,500					3,500
Scores Basis										
	Interest (Capital Project Only)				***************************************	***************************************	***************************************	***************************************	L	
4	Project Costs		18,401	15,371	15,371	6,025		A POLICE SERVICE		55,168
	General Contingency		6,500	2,028	7,472	4,500				20,500
	Specific Contingency									(-)
	Project Costs		24,901	17,399	22,843	10,525				75,668
Cash	Adjust to Cash Basis + / -	·			de la constanta de la constant				_	-
sh	Project Costs		24,901	17,399	22,843	10,525				75,668
	Currently Released		9,779							9,779
F	This Release	***************************************	15,122	17,399	***************************************	***************************************				32,521
Funding	Future Release				22,843	10,525			(0)	33,368
	Project Funding		24,901	17,399	22,843	10,525			(0)	75,668
	Note: Scores Basis	s = Cash E	Basis = Fund		Contract Con		y)		(9)	70,000
Budget	2009-2013 Business Plan		18,401	24,950		3,650	***************************************	· · · · · · · · · · · · · · · · · · ·		47,001
get	Variance to Business Plan	•	(0)	5,792		2,375				8,167
Q	Removal Costs included above					outerprassassing of the control of t			· ·	-
Other	Inventory to be written off			***************************************						-
	Spare Parts in Inventory	**************************************			placiferateship			-		

The estimated variance(s) to	he 2009-2013 Business Plan will be addressed through the portfolio mana	agement process
A PCRAF is not required	·	agoment process.

Reviewed By

D. Somerville Project Manager Date:

T. Chong

Strat IV Manager

2009 Jun 19

Date:



Page:

17 of 19

Filed: 2013-09-27 EB-2013-032

**BUSINESS CASE SUMMARY** 

Ex. F2-3-3 Attachment 1 Tab 6

# EQ Discovery Work & Scope Reduction Project 16 - 38458 Partial Release Business Case Summary D - BCS - 03651 - 10006 - R000

#### Attachment "B"

#### **Project Variance Analysis**

			Total	Project		
	OM&A	LTD Mar 2009	Last BCS Feb 2009	This BCS Apr 2009	Variance	Comments
	Project Mgmnt & Support		6,040	9,847	3,807	See Note 1.
	Engineering		21,620	23,921	2,301	See Note 1.
	Procurement		6,675	3,052	-3,623	See Note 2.
	Construction		14,685	14,848	163	
3	Other	100		3,500	3,500	See Note 3.
Scores					0	
0					0	
Racie					0	
2					0	
	Interest (Capital Project Only)				0	
	Project Costs (Scores Basis)	0	49,020	55,168	6,148	ALGORIUM EL SAMORAL EL MANAGE
	General Contingency		12,000	20,500	8,500	
	Specific Contingency		15,000		-15,000	
	Project Costs ( Scores Basis)	0	76,020	75,668	-352	
	<b>F</b>					
Other	Removal Costs included above				0	30
5	Inventory to be written off				0	
•	Spare Parts in Inventory				0	

0	Removal Costs included above		0	
5	Inventory to be written off		 0	
7	Spare Parts in Inventory		0	

#### Comments:

#### Note 1:

The developmental BCS assumed that there would be 12 modifications with the possibility of additional packages discovered during TBD / EQLDP preparation / revision. The cost estimates for these modification packages were based on preliminary information and contingency was included to account for the quality of estimates.

The projects scope now has 16 modification packages included in it and engineering has progressed on several packages allowing more detailed estimates to be prepared. This has resulted in additional funding requirements for design contracts and additional project management staff being hired to adequately monitor and progress the work.

#### Note 2:

Material costs are low compared to the total cost of the project because several modifications require only EQ qualified splice kits and/or qualified solenoid valves / transmitters which are relatively inexpensive. The installation cost is primarily driven by the labour requirements to perform and verify the work.

This \$3,500K is the estimated contract cost for the EQ completion assurance packages. This is not actually a variance, in the previous estimate this cost was included in the Contract - Design line.

Page: 18 of 19 Filed: 2013-09-27

**BUSINESS CASE SUMMARY** 

EB-2013-09-2 EB-2013-0321 Ex E2-3-3

Attachment 1 Tab 6

#### Attachment "C"

# Milestones and In Service Declarations

#### **Key Milestones**

Co	mpletion	Date	
Day	Mth	Yr	Description
30	Apr	2009	EQ Program Draft PEP
15	May	2009	CNSC Submission for Group 1 Heat Sinks
19	May	2009	NOC Meeting
21	May	2009	Partial Release approved by Board of Directors
30	Jun	2009	EQ Design Inputs Complete
30	Jun	2009	All Modifications & Baseline Maintenance (BM) & Dispositions Identified
30	Jun	2009	Strategic Sourcing Plan in place
30	Jul	2009	EQA Part II's Complete
30	Oct	2009	Long Lead Material Ordered (CAT ID identified)
30	Nov	2009	Technical Basis Documents Final Completion
15	Dec	2009	EQL Complete
15	Dec	2009	Room Conditions Complete
31	May	2010	Engineering Complete
31	May	2010	Final Release approved by Board of Directors
30	Jun	2010	Assessing Complete
30	Jun	2010	EQPR Complete
29	Oct	2010	All Baseline Maintenance Identified (last walk-down)
01	Dec	2010	Field Implementation Complete
30	Jun	2011	EQ Installation Instruction Complete
30	Jun	2011	EQ Training Program
30	Jun	2011	Closeout Complete

A Project Execution Plan (PEP) will be approved by Jun 2009

# In Service Declarations: (Capital Only)

Month	Year	Description	\$ 000's	%
				***************************************
				***************************************
***************************************				***************************************

Page: 19 of 19

BUSINESS CASE SUMMARY

# Attachment "D"

# Risk Probabilities Chart

Likelihood	Improbable	Unlikely	Possible	Likely	Probable
Probability	<= 1 in 1000	About 1 in 100	About 1 in 10	About 1 in 5	>= 3 in 4
Rank		2	~	7	ĸ

# Risk Impact Chart

Impact Rating	Financial	Project Schedule (12 months)	Quality	Corporate Reputation	Regulatory / Legal	Health & Safety	Environment	Nuclear Safety	
ro.	>80% of Total Project \$	> 90 day delay	Significant, unacceptable non- conformance requiring extensive rework	National and international adverse coverage or impacts	Non-compliance with potential for significant implications for personnel, potentially large damages or Criminal Charges  OR Potential loss of operating licenses	Potential for fatality(s)	Spill or release causing immediate and extended impact with off-site impacts, e.g.: Clean-up costs > \$15M Cat. A spill (>55 pts)	Loss or serious degradation of a safety system	
4	30% - 80% of Total Project \$	30 - 90 day delay	Unacceptable non- conformance requiring some rework, but not major	Long-term local or national impact	Legislative non-compliance with potential for fines, charges, and damages <b>OR</b> Major degradation of reputation with regulatory bodies	Potential for life- threatening critical injury or permanent total disability, including occupational disease	Exceedances resulting in charges or Director's Order Cat. A spill (45 - 55 pts) Public complaints with OPG implications Explosion and/or major fire	Reduced effectiveness of a safety system	
ო	15% - 30% of Total Project \$	10 - 30 day delay	Non-conformance bordering design tolerances, potential to require rework	Major local impact or minor national impact. Minor local damage	Systematic non-compliance with potential for fines OR Potential to cause strained relationship with regulator, increased surveillance and/or regulations	Potential for less serious critical injuries (e.g. fractures), permanent partial disabilities and temporary total disabilities of a significant nature	Cat. B spills Emission in exceedance of regulatory or legal limits Field orders or AMP's Public complaints with OPG implications Danger to health, life, or property	Reduced effectiveness of redundant safety system components	
8	5% - 15% of Total Project \$	3 - 10 day delay	Acceptable non- conformance, within design tolerances, no rework required	Complaints from local officials / politicians	Systematic non-compliance with impacts to project schedule OR Possibility of regulatory / legal implications	Potential for less serious temporary disabilities and injuries requiring off-site medical attention other than first-aid. Complete recovery by worker.	Cat. C spills - reportable Administrative infractions Public Complaints with plant level implications	Impact on a safety support or safety related system	
-	<5% of Total Project \$	< 3 day delay	Minimal impact on quality Routine non-conformance, can be easily dispositioned	Complaints from local public	Isolated non-compliance OR Routine approval / notification	No medical attention beyond first aid, no impairment to worker or complete recovery of worker.	Administrative, non-reportable events Cat. C spills non-reportable and spills resulting from Acts of God	Ex. F2-3-3 Attachment 1 Ta	Filed: 2013-09-2 EB-2013-0321

ab 6